BRUHAT BANGALORE MAHANAGARA PALIKE

APPROVED SCHEDULE - B

Name of work :- Proposed Constructing additional building of chock, Watch and Ward Building in Ward No.07,(Byatarayanapura) Kodigehalli sub division.

Sl. No.	Approved Qty.	Description	Unit	Approved Tender Rates of KRIDL	
				In Figures	In Words
1	11.76	KSRB 2-1.1 : Earth work in surface excavation in **ordinary soil** for levelling and lowering the ground manually (other than foundation of buildings, culverts, road drains and trenches of pipe lines and cables) and removing the excavated stuff to a distance not exceeding 50m and lift upto 1.50m. excavated surface levelled and neatly dressed , disposed earth to be levelled after breaking of clods and neatly dressed as per specifications.(P.No.5, I.No.2.1)	cum	124.02	Rupees One Hundred Twenty Four and Two Paise Only
2	8.78	KSRB 2-2.2 : Earth work excavation for foundation of buildings, culverts, water supply, sanitary lines and electrical conduits either in pits or in trenches, 1.5m and above in width, **in hard soil**, exceeding 1.5m in depth including dressing the bottom and sides of pits and trenches, stacking the excavated soil clear from edges of excavation with all lead upto 50m after breaking of clods complete as per specifications.(P.No.5, I.No.2.4)	cum	223.66	Rupees Two Hundred Twenty Three and Sixty Six Paise Only
3	20.55	Lead for disposal of earth shall be payable at Carriage rates (Lead & Lift) by mechanical means including loading and unloading up to 15kms.(Refer Table. Page No.150)	cum	100.60	Rupees One Hundred and Sixty Paise Only
4	10.37	KSRB 4-1.2 : Providing and laying in position plain cement concrete of mix M 10(1:3:6) with OPC cement @ 220kgs, with 40mm and down size graded granite metal coarse aggregates @ 0.892 cum and fine aggregates @ 0.465 cum machine mixed, concrete laid in layers not exceeding 15cms thick well compacted, in foundation and plinth, including cost of all materials, labour, HOM of machinery, curing complete as per specifications. (P-12 I.No.4.3)	cum	4413.84	Rupees Four Thousand Four Hundred Thirteen and Eighty Four Paise Only
5	3.95	KSRB 5.2-3 : Providing and constructing granite/ trap/basalt size stone masonry in foundation in CM 1:6 stone hammed dressed in courses not less than 20cms high, bond stones at two m apart in each course including cost of materials labour, curing etc., complete as per specifications. (P.25, I.No. 5.6)	cum	3484.22	Rupees Three Thousand Four Hundred Eighty Four and Twenty Two Paise Only

Assistant Executive Engineer
Byatarayanapura Sub-division
KRIDL, BBMP, Bangalore

Executive Engineer
Byatarayanapura Division
Yelahanka Zone, B.B.M.P.
Bangalore - 560 092

6	0.28	KSRB 4-1.6 : Providing and laying in position plain cement concrete of mix M15(1:2:4) with cement @ 240kgs, with 20mm and down size graded granite metal coarse aggregates @ 0.878 cum and fine aggregates @ 0.459 cum machine mixed, concrete laid in layers not exceeding 15cms thick well compacted, in foundation and plinth and cills, including cost of all materials, labour, HOM of machinery, curing complete as per specifications. (P-12 I.No.4.6)	cum	4690.50	Rupees Four Thousand Six Hundred Ninety and Fifty Paise Only
7	36.85	KSRB 4-2.2 : Providing and laying in position reinforced cement concrete of design mix M20(1:1.5:3) with OPC cement @ 320kgs, with 20mm and down size graded granie metal coarse aggregates @0.878cum and fine aggregates @ 0.459cum, with superplastisiser @ 3lts confirming to IS9103-1999 Reaffirmed-2008, machine mixed, concrete laid in layers not exceeding 15 cms thick, vibrated for all works in foundation plinth and ground floor level for roof slabs, staircase linels, retaining walls, return walls, walls(any thickness) including attached plasters, columns, piers, abutments, pillars, posts, struts, buttresses, string or lacing courses, parapets, coping, bed blocks, anchor blocks, plain window cills, fillets etc., including cost of all materials, labhour, HOM of machinery, curing, complete as per specifications. (P.No.13,I.No.4.11)	cum	5535.32	Rupees Five Thousand Five Hundred Thirty Five and Thirty Two Paise Only
8	316.40	KSRB 4-6.2Providing and removing centering, shuttering, strutting, propping etc., and removal form work for flat surface such as suspended floors, roofs, landings, balconies and like, thickness upto 200mm including cost of materials, labhour complete as per specification.(P.No.16,I.No.4.29)	Sqm	284.08	Rupees Two Hundred Eighty Four and Eight Paise Only
9	29.48	KSRB 4.9.2 : Providing T.M.T bars Fe 500 steel reinforcement for R.C.C work including straightening, cutting, bending, hooking, placing in position, lapping and / or welding wherever required, tying with binding wiere and anchoring to the adjoining members wherever necessary complete as per design (laps, hooks and wastage shall not be measured and paid) cost of materials labour HOM of machinery complete (P-19, I No. 4.46.2)	Qtl	7312.94	Rupees Seven Thousand Three Hundred Twelve and Ninety Four Paise Only
10	8.18	Providing RCC loft (atta) 7.5cms thick with cement concrete design mix M20 using clean granite or trap jelly of 20mm and down size with necessary reinforcement at 20cms centre to centre as per design including form work, centring, curing, finishing the exposed faces with cement mortar (1:3) etc., complete (exlusive of cost of steel and fabrication charges).(P.20, I.No. 4.54)	Sqm	458.98	Rupees Four Hundred Fifty Eight and Ninety Eight Paise Only

Assistant Executive Engineer
Byatarayanapura Sub-division
KRIDL, BBMP, Bangalore

Executive Engineer
Byatarayanapura Division
Yelahanka Zone, B.B.M.P.
Bangalore - 560 092

11	67.23	KSRB 6-2.4 : Providing and constructing burnt brick masonry with approved quality of class designation 50 with cement mortar 1:4 for basement and super structure including cost of materials labour charges, scaffolding, curing etc., complete as per specifications. (P.No.30, I No. 6.7)	cum	5916.92	Rupees Five Thousand Nine Hundred Sixteen and Ninety Two Paise Only
12	22.64	KSRB 6-7.2 : Construction of partition wall 11.2cms thick with non-modular table moulded burnt bricks of class designation 50 with cement mortar 1:4 including providing and fixing plaster mesh manufactured out of hot dipped galvanised iron of nominal thickness 0.35mm. 100 mm. wide as per I.S. 2212/1991 at 7.5m. c to c including cost of materials,labhour charges, scaffolding, curing complete as per specifications.(P.No.33,I.No.6.24)	Sqm	799.24	Rupees Seven Hundred Ninety Nine and Twenty Four Paise Only
13	126.90	KSRB 15-3-13 : Providing 12mm thick cement plaster in single coat with cement mortar 1:3, to ceiling including rounding off corners wherever required smooth rendering,: providing and removing scaffolding, including cost of materials,labhour, curing complete as per specifications.(P.No.123, I.No.15.21)	Sqm	163.24	Rupees One Hundred Sixty Three and Twenty Four Paise Only
14	401.45	KSRB 15-3.7 : Providing 18mm thick cement plaster in single coat with cement mortar 1:3 to brick masonry including rounding off corners wherever required smooth rendering,: providing and removing scaffolding, including cost of materials,labhour, curing complete as per specifications.(P.No.122, I.No.15.15)	Sqm	209.88	Rupees Two Hundred Nine and Eighty Eight Paise Only
15	528.35	KSRB 15-7 : Providing and lime rendering for plastering to wall and ceiling including cost of materials, labhour , curing complete as per specifications(P.No.124,I.No.15.33)	Sqm	19.08	Rupees Nineteen and Eight Paise Only
16	337.96	KSRB 15-13 : Providing 20mm thick cement plaster in single coat with cement mortar 1:3 to brick masonry including rounding off corners wherever required smooth rendering,: providing and removing scaffolding, including cost of materials,labhour, curing complete as per specifications.(P.No.123, I.No.15.18)	cum	223.66	Rupees Two Hundred Twenty Three and Sixty Six Paise Only
17	57.92	KSRB 15-5.1 : Providing rough cement plastering 15mm thick in single coat with cement mortar 1:4, to brick masonry for base for of dadooing works with sand of approved quality, providing and removing scaffolding, including cost of materials, labhour, curing complete as per specifications.(P.No.123,I.No.15.30)	Sqm	150.52	Rupees One Hundred Fifty and Fifty Two Paise Only
18	57.92	KSRB 14-17.2 : Providing skirting, dado, rises of steps with colour glazed tiles 30x45cms 6mm thick with border of size 30x 10mm thick cement plaster 1:3 and jointed with white cement slurry over rough plaster surface (excluding cost of rough plastered surface which should be measured and paid separately) using glazed tiles of approved make and size including cost of materials, labour, complete as per specifications (P-116, I No. 14.41.3)	Sqm	1261.40	Rupees One Thousand Two Hundred Sixty One and Forty Paise Only

Assistant Executive Engineer
Byatarayanapura Sub-division
KRIDL, BBMP, Bangalore

Executive Engineer
Byatarayanapura Division
Yelahanka Zone, B.B.M.P.
Bangalore - 560 092

19	11.57	KSRB 14.14-2 : Providing Ceramic tiles 30x30cms of approved make, shade and size for flooring, treads of steps and landings laid on bed of 12mm thick, cement mortar 1:3 mix, flush pointing with white cement using colour pigment, including cost of materials,labhour,curing,complete as per specifications.(P.No.115,I.No.14.36.2).	Sqm	933.86	Rupees Nine Hundred Thirty Three and Eighty Six Paise Only
20	3.26	KSRB 4-5 : Providing lath plaster with cement mortar 1:3, 5cm thick with 6mm dia mild steel bars at 20 cms. C to c both horizontally and vertically fixed chicken mesh for drop chajja, facia, backing to cup boards including cost of all materials, curing, complete as per specifications.(P.No.16,I.No.4.27)	Sqm	895.70	Rupees Eight Hundred Ninety Five and Seventy Paise Only
21	0.77	KSRB 9.4-2 : Providing Honne Wood frames of windows, clerestory windows, ventilators and other frames, wrought, framed or assembled including making plaster groves (excluding cost of cement concrete and side clamps) but including cost of materials, labour HOM of machineries complete (P.56, I.No. 9.11)	cum	105456.22	Rupees One Hundred Five Thousand Four Hundred Fifty Six and Twenty Two Paise Only
22	11.34	KSRB 9-7.1 : Providing and fixing in position fully panelled Honne wood shutters for door,styles and rails of 30mm.thick with bottom and lock rails 180mm wide top rail and styles 100mm wide as per drawing and panels of 25mm thick including cost of materials,labhour, HOM of machineries complete as per specifications.(excluding cost of fixtures).(P.No.57,I.No.9.21)	Sqm	3995.14	Rupees Three Thousand Nine Hundred Ninety Five and Fourteen Paise Only
23	29.00	SOLID PVC DOOR FRAME : Providing and fixing factory made PVC door frame of size 50x47mm with a wall thickness of 5mm, made out of extruded 5mm rigid PVC foam sheet metered cut at corners and jointed 2 nos. of 150 mm long brackets of 15mm x 15mm MS square tube the entire door frame to be reinforced with 19mm x 19mm gauge. The frame to be fixed to the wall using MS screws of 65/80 mm size complete as per manufactures specifications.(P.No.63,I.No.9.84)	m	545.90	Rupees Five Hundred Forty Five and Ninety Paise Only
24	7.88	SOLID PANEL PVC DOOR SHUTTER : Providing and fixing 30mm factory made rigid foam panelled door shutter made of MS tube of 19 gauge thickness size 19mm x 19mm from styles and 15mm x 15mm for top and bottome rails, covered with heat moulded PVC channel of 5mm thick sheet and 30mm x 50mm wide to form styles and 5mm thick 75mm wide PVC sheets for top rails, lock rails and bottom rails, on either side and 5mm thick 20mm wide PVC sheet as gap inset for top rails and bottom rails panelling of 5mm thick PVC sheet fitted in the MS frame, seales to the styles and rails with 5 x 30mm PVC sheet beading on either side and joined together with solvent cement adhesive etc., complete as per manufactures specifications and directions as per engineer-in-charge fixed to frames with 3 nos of 75mm aluminium hinge.(P.No.63,I.No.9.83).	Sqm	3343.24	Rupees Three Thousand Three Hundred Forty Three and Twenty Four Paise Only

Assistant Executive Engineer
Byatarayanapura Sub-division
KRIDL, BBMP, Bangalore

Executive Engineer
Byatarayanapura Division
Yelahanka Zone, B.B.M.P.
Bangalore - 560 092

25	1.80	KSRB 7.8 : Providing and fixing in position in cement concrete 1:3:6 steel glazed window and ventilators side hung/top hung 2/3 openable 1/3 fixed as per approved drawings using Z angles of 25x33x3mm, weighing 1.419 kg/m both for outer and inner frames and central mullion section of size 25x46x3mm, weighing 2.28 kg/m all duly providing T section 19x19x3mm weighing 0.839 kg/m for glazing of windows, not more than 34cms. c to c including providing and fixing 4mm. thick reeded glass with teakwood beading of required size, all steel sections should confirm to I.S.7452:1990, 4nos. of holdfasts of approved size, section should be cut of length welded and grinded electrically subdividing frames of unit shall be tenonned and revetted into the frames electrically. All the steel surface shall be thoroughly cleaned free of rust painted with one coat of anti-corrosive paint and finishing two coats of ready mix paint of approved colour and make including cost of materials, fixtures, labhour charges and HOM of machinery complete as per specifications.(P.No.37,I.No.7.8)	Sqm	3058.10	Rupees Three Thousand Fifty Eight and Ten Paise Only
26	12.80	Providing and fixing M.S.Hand railing for Balcony with 50mm dia. M.S.hollow pipe of 14 gauge, welded to 20mmx20mm M.S.square rod placed vertically, spaced 100mm at regular intervals of 600mm. These vertical rods laterally tied to 3 horizontal rods spaced at equal interval. Theses assembly is fixed to concrete by using expansion bolts and welding the same to reinforcement bars and making good the surface. All the joints and sections should be cut to length, welded and grinded wherever necessary etc., complete. The work includes cost of all materials, labhour charges for all items of work, hire charges for welding, cutting and grinding equipment, and electricity charges etc., complete as per specification and drawing.(P.No.47,I.No.7.35)	Sqm	2664.84	Rupees Two Thousand Six Hundred Sixty Four and Eighty Four Paise Only
27	376.11	KSRB 7.9 :Providing and fixing in position MS grill work for windows & ventilators weighing 21 kg/Sqm using MS flats or MS square rods or combination of MS flats & square rods as per design drawing including cutting steel sections welding the same to required pattern with a coat of red lead primer, including cost of materials, fixtures, labhour charges and HOM of machineries complete as per specifications.(P.No.37,I.No.7.9).	kgs	95.40	Rupees Ninety Five and Forty Paise Only

Assistant Executive Engineer
Byatarayanapura Sub-division
KRIDL, BBMP, Bangalore

Executive Engineer
Byatarayanapura Division
Yelahanka Zone, B.B.M.P.
Bangalore - 560 092

28	13.77	KSRB 7.10 : Providing and fixing in position anodized aluminium windows and ventilators as per approved drawings with sliding shutters using double track window frame section of size 61.85x31.75mm. With 1.2mm thick, bottom section weight 0.695 kg/m; and shutter comprising top and bottom section of size 40mmx18mm,1.25mm thick 0.417kg/m; shutter interlock section 40mmx26.7mm, 1.1mm thick, weight 0.469kg/m, the shutters mounted on nylon rollers with approved quality of fixtures such as aluminium handles tower bolts etc; and providing and fixing 5.5mm thick plain glass for shutters fitted with rubber beading aluminium sections anodised 12 to 15 microns, including cutting to required length, joints mitred subdividing the frame tenonned and rivetted in the assembled frame stiffened with end beams/cills as the case may be with necessary steel screws, raul plugs, or teak wood gatties including cutting masonry or concrete and making good the original surface using cement mortar, aluminium sections pretreated for removal of any rush and coated with greasy for non adhesion of mortor and other sticky materials:(this fixtures, labhour and HOM at machinery complete as per specifications.Using alluminium section powdered	Sqm	3832.96	Rupees Three Thousand Eight Hundred Thirty Two and Ninety Six Paise Only
29	9.90	Providing and fixing M.S.Gate as per Chief Architect drawing, usin 50x50mm 14 gauge M.S.hollow pipe frame work bent to ornamental shape as shown in the drawing and 35mmx6mm and 16x16mm square rods for verticals alternatively spaced at 4 cms c/c in two halves and 40mmx6mm M.S.flat for horizontal member and at the top cast iron spikes are provided at alternative vertical members as shown in the drawing etc., complete. all the steel surface should be thoroughly cleaned free of rust and painted with anti corrosive paint (shop paint) etc., complete. The work includes cost of all materials, labhour charges for all items of work, hire charges, with lead and lift, laoding and unloading charges, etc., complete as per specifications.(P.No.47,I.No.7.37)	each	3281.76	Rupees Three Thousand Two Hundred Eighty One and Seventy Six Paise Only
30	2.20	KSRB 7.4 : Providing and fixing 1mm thick M.S. sheet garage door with frame and diagonal braces of size 40x40x6mm angle Iron, 3.15mm thick M.S.gusset plates at the junctions and corners, with handles, stoppers and locking arrangements etc., including applying a priming coat of red lead paint cost of materials, labhour, HOM of machinery complete as per specification(P.No.36,I.No.7.3)	Sqm	2745.40	Rupees Two Thousand Seven Hundred Forty Five and Forty Paise Only
31	13.50	KSRB 8.3-2 : Providing and laying to required line and slope roofing with semi-corrugated(trafford) asbestos cement sheet 6mm.thick fixed with galvanised iron J or L hooks, and nut 8mm dia C.I.Plain and bitumen washers, over the existing purlins, rafters and trussess including cost of materials, labhour, complete as per specifications.(P.No.51,I.No.8.6)	Sqm	397.50	Rupees Three Hundred Ninety Seven and Fifty Paise Only

Assistant Executive Engineer
Byatarayanapura Sub-division
KRIDL, BBMP, Bangalore

Executive Engineer
Byatarayanapura Division
Yelahanka Zone, B.B.M.P.
Bangalore - 560 092

32	**152.62**	Providing and fixing granite flooring in combination of 19mm thick (Avg) gang saw water cut LAKARED granite with 86% and with 14% of 19mm thick (avg) Black granite in CM 1:4 proportion with a coat of rough plastering using CM 1:4, cut to required shape, pattern with paper joints, finished with cement mortar using white cement and colour pigments to match the colour of slab making through jointing with sealant, grooves in joints including cost of curing etc., complete including cost of conveyance of all materials, labhour for all items of work, HOM of equipment etc., complete as per specification.(P.No.118,I.No.14.58)	Sqm	**5283.36**	Rupees Five Thousand Two Hundred Eighty Three and Thirty Six Paise Only
33	33.30	Providing half nosing for 20mm thick granite slab using required machinery including cost and conveyance of all materials, labhour for all items of work, HOM of equipments etc., complete as per specifications.(P.No.118,I.No.14.56)	Sqm	130.38	Rupees One Hundred Thirty and Thirty Eight Paise Only
34	112.70	KSRB 14.7-3 : Providing and laying flooring 40mm thick, with an under layer of 30mm 1:2:4 cement concrete, using broken granite metal of 12.5mm nominal size and top layer of 10mm thick plaster with cement mortar 1:3, finished with floating coat of cement, including cost of materials, labhour, curing, complete as per specifications.(P.No.110,I.No.14.10)	m	442.02	Rupees Four Hundred Forty Two and Two Paise Only
35	528.35	KSRB 15-14.4 : Providing and applying painting in two coats with plastic emulsion paint of approved brand on wall surface to give an even approved shade after thoroughly brushing the surface, free from mortar drops and other foreign matter including preparing the surface even and sand paper smooth, cost of materials, labhour complete as per specifications.with primer.(P.No.126,I.No.15.51.2)	Sqm	79.50	Rupees Seventy Nine and Fifty Paise Only
36	337.96	Providing and finishing external walls in two coats with primer water proof cement paint of approved brand and shade to give an even shade after throughly brooming the surface to remove all dirt and loose powdered material, free from mortar drops and other foreign matter cost of materials, labour, complete as per specification (P-127, I.No. 15.53.2)	Sqm	78.44	Rupees Seventy Eight and Forty Four Paise Only
37	70.29	Applying priming coat over new wood surface and / or wood based surface with white lead paint priming including preparing the surface after throughly cleaning oil, grease, dirt and foreign matter, sand papering and knotting, ready mix paint including cost of materials, labour, complete. (P.No.127, I.No.15.55)	Sqm	29.68	Rupees Twenty Nine and Sixty Eight Paise Only
38	70.29	Providing and applying painting two coats (excluding priming cost) on new wood surface and / or wood based surface with enamel paint to give an even shade, cleaning the surface of all dirt, dust and foreign matter, sand papering including cost of materials, labour etc., complete as per specifications. (P.No.128, I.No. 15.60.1)	Sqm	78.44	Rupees Seventy Eight and Forty Four Paise Only

Assistant Executive Engineer
Byatarayanapura Sub-division
KRIDL, BBMP, Bangalore

Executive Engineer
Byatarayanapura Division
Yelahanka Zone, B.B.M.P.
Bangalore - 560 092

39	144.19	KSRB 10-3 : Providing and laying integral cement based waterproofing treatment including preparation of surface as required for treatment of roofs, balconies, terraces etc., consisting of following application. (a) Applying and grouting a slurry coat of neat cement using 2.75 kg/sqm of cement admixed with proprietary water proofing compound confirming to IS:2645 over the RCC slab after cleaning the surface before treatment. (b) Laying cement concrete using broken brick bats 25mm to 100 size with 50% of cement mortar 1:5 admixed with proprietary water proofing compound confirming IS:2645 over 20mm thick layer of cement mortar 1:5 admixed with proprietary water proofing compound to required slope and treating similarly the adjoining walls upto 300mm height including rounding off junctions of walls and slabs.(c) After two days of proper curing,applying a second coat of cement slurry admixed with proprietary water proofing compound. (d) Finishing the surface with 20mm thick jointless cement moratr of mix 1:4 admixed with proprietary water proofing cement slurry and making of 300x300mm square. (e) The whole terrace so finished shall be flooded with water for a	Sqm	779.10	Rupees Seven Hundred Seventy Nine and Ten Paise Only
40	14.00	KSRB 8.6-8 : Providing and fixing on wall surface 4.0kg/sq.cm H.D.P.E rain down water pipes 110mm outer dia approved make and brand with necessary specials like shoes, bends, and offsets fixed with iron clamps, wall plugs, screws, including cost of materials, labhour, complete as per specifications.(P.No.52, I.No.8.19)	Nos	595.72	Rupees Five Hundred Ninety Five and Seventy Two Paise Only
41	2.00	KSRB 13-11.1 : Providing and placing on terrace, polyethylene water storage tanks with manhole lid and suitable locking arrangements, making holes of suitable diameter for inlet, outlet and over flow pipes, including cost of all materials, labhour, transport charges, HOM of equipments and testing complete as per specifications.(For 1000 litre capacity).(P.No.103.I.No.13.78).	pan	8831.92	Rupees Eight Thousand Eight Hundred Thirty One and Ninety Two Paise Only
42	2.00	KSRB 11-4 : Providing and fixing white vitreous china clay, water closet Orissa pattern of size 580x440mm with integral type foot rests, 100mm S or P trap,(approved make) cutting and making good the wall and floor wherever required,including cost of materials, labhour complete as per specifications.(P.No.79, I.No.12.4)	each	2271.58	Rupees Two Thousand Two Hundred Seventy One and Fifty Eight Paise Only
43	3.00	KSRB 11-2 : Providing and fixing white vitreous china clay, water closet Orissa pattern of size 580x440mm with integral type foot rests, 100mm S or P trap, 10 litre low level, P.V.C flushing cistern (all are approved make) with fittings, C.I/M.S brackets, 32mm diameter flush pipe fittings and clamps, overflow arrangements with special and 25mm mosquito proof coupling of approved design, painting of fittings and brackets, cutting and making good the wall and floor wherever required, including cost of materials, labhour complete as per specifications.(P.No.79, I.No.12.2)	each	4441.40	Rupees Four Thousand Four Hundred Forty One and Forty Paise Only

Assistant Executive Engineer
Byatarayanapura Sub-division
KRIDL, BBMP, Bangalore

Executive Engineer
Byatarayanapura Div
Yelahanka Zone, B.B.M.P.
Bangalore - 560 092

44	2.00	KSRB 11-2 : Providing and fixing white vitreous china clay, water closet Orissa pattern of size 580x440mm with integral type foot rests, 100mm S or P trap, 10 litre low level, P.V.C flushing cistern (all are approved make) with fittings, C.I/M.S brackets, 32mm diameter flush pipe fittings and clamps, overflow arrangements with special and 25mm mosquito proof coupling of approved design, painting of fittings and brackets, cutting and making good the wall and floor wherever required, including cost of materials, labhour complete as per specifications.(P.No.79, I.No.12.2)	each	4441.40	Rupees Four Thousand Four Hundred Forty One and Forty Paise Only
45	2.00	KSRB 11-7.2 : Providing and fixing white vitreous china clay, flat back, lipped front urinal basin 430x260x350mm with 5 litres PVC automatic flushing cistern, C.I/M.S brackets, standard flush pipe and C.P.brass spreaders with brass unions and G.I.clamps complete painting of fittings and brackets, cutting and making good the wall and floor wherever required, including cost of materials, labhour complete as per specifications.(P.No.80, I.No.12.7)	each	2900.16	Rupees Two Thousand Nine Hundred and Sixteen Paise Only
46	5.00	KSRB 11-11.1 : Providing and fixing white vitreous china clay, flat back wash basin size 630x450mm with a pair of 15mm C.P.brass pillar taps with C.I./ M.S brackets, 32mm C.P. brass waste of standard pattern, painting of fittings and brackets, cutting and making good the wall and floor wherever required, including cost of materials, labhour complete as per specifications.(P.No.82,I.No.12.23)	each	3773.60	Rupees Three Thousand Seven Hundred Seventy Three and Sixty Paise Only
47	5.00	KSRB 11-15.3 : Providing and fixing 453x357mm rectangular shape mirror with plastic moulded frame of approved make and shade with 6mm thick hard board backing including cost of materials, labhour complete as per specifications.(P.No.85,I.No.12.41)	Unit	1204.16	Rupees One Thousand Two Hundred Four and Sixteen Paise Only
48	5.00	KSRB 11-17-1 : Providing and fixing C.P. brass towel rail 600mm length, 20mm dia with C.P.brackets, fixed to wooden cleats with C.P.brass screws including cost of materials,labhour complete as per specifications.(P.No.85,I.No.12.46).	Unit	719.74	Rupees Seven Hundred Nineteen and Seventy Four Paise Only
49	40.00	KSRB 13-8.9 : Providing and fixing to wall, ceiling and floor high density polyethlene pipes 6.00 kgf/sq.cm working pressure 90mm outside diameter with special flange, compression type fittings, wall clips, making good the wall, ceiling and floor, including cost of all materials, labhour charges, HOM of equipments and testing complete as per specifications. (P.No.102,I.No.13.73.3)	m	491.84	Rupees Four Hundred Ninety One and Eighty Four Paise Only

Assistant Executive Engineer
Byatarayanapura Sub-division
KRIDL, BBMP, Bangalore

Executive Engineer
Byatarayanapura Division
Yelahanka Zone, B.B.M.P
Bangalore - 560 092

50	25.00	KSRB 13-8.9 : Providing and fixing to wall, ceiling and floor high density polyethlene pipes 6.00 kgf/sq.cm working pressure 140mm outside diameter with special flange, compression type fittings, wall clips, making good the wall, ceiling and floor, including cost of all materials, labhour charges, HOM of equipments and testing complete as per specifications. (P.No.102,I.No.13.73.5)	m	748.36	Rupees Seven Hundred Forty Eight and Thirty Six Paise Only
51	10.00	Providing Gun metal pillar cocks 15mm dia of I class confirming to ISI specifications and fixing them in position as per directions including cost of materials and fixtures and conveyence to spot.(P.No.104,I.No.13.80).	each	259.70	Rupees Two Hundred Fifty Nine and Seventy Paise Only
52	50.00	KSRB-1.2 : Providing and fixing to wall, ceiling and floor galvanised/mild steel tube 20mm dia nominal bore with of fittings(medium grade weight 1.65kg/m) B class including cost of all materials, labhour charges, HOM of equipments and testing complete as per specification.(P.No.94, I.No.13.2)	m	224.72	Rupees Two Hundred Twenty Four and Seventy Two Paise Only
53	30.00	KSRB-1.3 : Providing and fixing to wall, ceiling and floor galvanised/mild steel tube 25mm dia nominal bore with of fittings(medium grade weight 2.51kg/m) B class including cost of all materials, labhour charges, HOM of equipments and testing complete as per specification.(P.No.94, I.No.13.3)	m	310.58	Rupees Three Hundred Ten and Fifty Eight Paise Only
54	15.00	KSRB 13-1.3 : Providing and fixing to wall, ceiling and floor galvanised/mild steel tube 32mm dia nominal bore with of fittings(medium grade weight 3.23kg/m) B class including cost of all materials, labhour charges, HOM of equipments and testing complete as per specification.(P.No.94, I.No.13.4)	m	354.04	Rupees Three Hundred Fifty Four and Four Paise Only
55	1.00	KSRB 13-6.4-2 : Providing and fixing in position brass ball valve high or low pressure with plastic float of approved quality 20mm nominal bore including cost of all materials, labhour and HOM of equipements with all leads complete as per specifications.(P.No.98,I.No.13.41).	each	419.76	Rupees Four Hundred Nineteen and Seventy Six Paise Only
56	15.00	KSRB 13-6.2-2 : Providing and fixing in position brass stock cock of approved quality 20mm nominal bore including cost of all materials, labhour and HOM of equipements with all leads complete as per specifications.(P.No.96, I.No.13.27).	each	169.60	Rupees One Hundred Sixty Nine and Sixty Paise Only
57	2.00	KSRB 13-6.3-2 : Providing and fixing in position brass gate ball valve with C.I.wheel of aproved quality (screwd end) 20mm nominal bore including cost of all materials, labhour and HOM of equipements with all leads complete as per specifications.(P.No.97, I.No.13.33).	each	428.24	Rupees Four Hundred Twenty Eight and Twenty Four Paise Only
58	8.00	Providing stoneware gully trap 15cms x 10cms of approved quality and make fixing in M15 and plastering with CM 1:3 wherever necessary.(Rate includes cost of all material, fixture and lead)(P.No.92,I.No.12.112.2)	each	286.20	Rupees Two Hundred Eighty Six and Twenty Paise Only
59	12.00	Providing and fixing 7.5cm to 15 cms dia NP grating 100 mm dia.(P.No.92,I.No.12.111)	each	169.60	Rupees One Hundred Sixty Nine and Sixty Paise Only

Assistant Executive Engineer
Byatarayanapura Sub-division
KRIDL, BBMP, Bangalore

Executive Engineer
Byatarayanapura Division
Yelahanka Zone, B.B.M.P.
Bangalore - 560 092

60	4.00	KSRB 12-8.1 : Constructing brick masonry inspection chamber 600x600mm and 450mm depth, (clear inside dimension) for single pipeline, using table moulded non-modular bricks of class designation 50 in cement mortar 1:5, C.I.cover with frame(light duty) 600x600mm inner dimensions, total weight cover with frame to be not less than 38kg(weight of cover with frame 15kg) R.C.C. top slab with cement 1:2:4 mix 20mm and downsize granite metal, foundation concrete 1:5:10 with 40mm and downsize granite metal inside plastering 12mm thick with cement mortar 1:3, finish smooth with a floating coat on walls and bed concrete complete as per standard including cost of materials, labhour charges, curing complete as per specifications.(P.No.74,I.No.11.50.1)	each	8063.42	Rupees Eight Thousand Sixty Three and Forty Two Paise Only
61	20.00	Hold fasts MS.(P.No.XIV,S.L.No.396,Code.No.0189)	each	38.00	Rupees Thirty Eight Only
62	20.00	Hinges 5" Heavy duty.(P.No.XIV,S.L.No.395,Code.No.0188)	each	37.00	Rupees Thirty Seven Only
63	12.00	Handles powder coated 150mm.(P.No.XIV,S.L.No.393,Code.No.0178)	each	56.00	Rupees Fifty Six Only
64	7.00	Locking arrangements.(P.No.XIV,S.L.No.397,Code.No.0220)	each	633.00	Rupees Six Hundred Thirty Three Only
65	50.00	Providing 2 legged scaffolding for stone maosnry work using 10-15 cms. Dia best quality casurian poles of 4m over all length(3m+0.5m projection+0.5m + Projection+0.5m. In to the ground) the distance between two rows being 1.25m and spacing of posts being 2m c to c including longitudinal and transverce middle braces to step up and providing platform with casurina poles, forms tied up using coir rope complete as per specifications.(P.No.18,I.No.4.43.1)	Mtr	239.56	Rupees Two Hundred Thirty Nine and Fifty Six Paise Only
66	17.90	Providing and laying/fixing cement base, precast, pre polished cement concrete designer tiles 25mm thick confirming to IS 1237 heavy duty tiles for flooring, treads of steps and landing, laid on a bed of 12mm thick cement mortar 1:3, mis finished with flush pointing using white cement, including cost of materials, including cutting, grinding the edge to half/full round wherever required, labhour, complete as per specification.(P.No.119,I.No.14.62)	Sqm	1028.20	Rupees One Thousand Twenty Eight and Twenty Paise Only
67	90.00	Providing and fixing pre cast solid cement concrete kerb stones made out of C.C. 1:2:4 witht top and bottom width 114 and 165 mm respectively, 400mm high and 450mm in length finished with CM 1:3 plastering and finishing cutting, including formwork curing, including cost of all materials, labhour, hire charges of machinery, loading, unloading, lead and lift, trasportation etc., complete(P.No.28, I.No.5.30.5.29(b))	Nos	262.88	Rupees Two Hundred Sixty Two and Eighty Eight Paise Only

Assistant Executive Engineer
Byatarayanapura Sub-division
KRIDL, BBMP, Bangalore

Executive Engineer
Byatarayanapura - Asst
Ex Zone, B.B.M.P.
Bangalore - 560 092

68	7.74	KSRB 8.7-5 : Providing and fixing in position 12mm thick plaster of paris (Gypsum anhydrous) for ceiling flat surface with ceiling tiles upto a height of 5m above floor level wooden frames and rendered smooth with plaster of paris (frame work to be measured and paid for separately) including cost of materials, labhour, curing complete as per specifications.(P.No.53,I.No.8.24)	Sqm	782.28	Rupees Seven Hundred Eighty Two and Twenty Eight Paise Only
69	**9.38**	KSRB-7.1: Providing and fixing in position collapsible steel shutters with single or double leaf with vertical channel 20mm x 10mm x 2mm braced with flat iron diagonals 20mm x5mm size, with top and bottom rails of T iron sections of 40x40x6 mm with 38mm dia steel pulleys complete with bolt and nuts, locking arrangements, stoppers, handles on both sides with 7.5cms openings at 10cms c to c applying a priming coat of red lead pint cost of materials, labour HOM of machinery complete size of gate 2.4m x 1.4m (P-36, I No. 7.1)	Sqm	**4306.78**	Rupees Four Thousand Three Hundred Six and Seventy Eight Paise Only
70	3.00	Providing and supplying of Executive Extension Table-Celeon series of size 1810x422x952mm.(As per approved Data rate)	Nos	57073.00	Rupees Fifty Seven Thousand Seventy Three Only
71	3.00	Providing and supplying of executive High back Chair in Leatherite.(As per Approved Data rate)	Nos	14430.00	Rupees Fourteen Thousand Four Hundred Thirty Only
72	7.00	Providing and supplying of Cushion Chairs(As per approved Data rate)	Nos	4160.00	Rupees Four Thousand One Hundred Sixty Only
73	3.00	Providing and supplying of Metal Sofa Three Seater with Powder coated Legs.(As per approved data rate)	Nos	21718.00	Rupees Twenty One Thousand Seven Hundred Eighteen Only
74	2.00	Providing and supplying of Wooden Sofa of Single Seater.(As per approved data rate)	Nos	11318.00	Rupees Eleven Thousand Three Hundred Eighteen Only
75	1.00	Providing and supplying of Wooden Sofa of Three Seater.(As per approved data rate)	Nos	23743.00	Rupees Twenty Three Thousand Seven Hundred Forty Three Only

Signature of the Contractor

Assistant Executive Engineer
Byatarayanapura Sub-division
KRIDL, BBMP, Bangalore

Executive Engineer
Byarayanapura Division
BBMP, Bangalore - 92